

Additions and Alternations to the Saxe Middle School
RFP #2016-05 – Telecommunications Infrastructure Installation
State Project No. 090-0048 EA/CV
Addendum #1 – December 9, 2016
Page 1 of 2

Drawing Change to Sheet IT-112:

The 'TV' drop on the North wall of FAB LAB B105 is being relocated to the East Wall. The emergency eye wash is removed from this location.

Responses to questions received are as follows:

Q1: Drawings IT-001 and IT-301 refer to Specification Section 271xxx for part numbers and quantities of certain items. Is this Specification Section available?

A1: All specifications are included in the Project Manual.

Q2: What type of cable is required for Audio? Is there a one line diagram available showing the Audio and how the Volume Control, powered/un-powered speakers and power supplies interconnect?

*A2: Refer to manufacturer's instruction manual that can be viewed at the link below. Note that these instructions are specific to the non-Bluetooth model, but the wiring requirements are identical.
http://owi-inc.com/uploads/3/4/8/6/34865657/amp-er2tr6_manual_082516.pdf*

Q3: Who is responsible for the floor cores and sleeves between the 1st and 2nd floors in Area B?

A3: Floor cores and sleeves will be provided by Electrical Contractor.

Q4: Is it safe to assume that the Technology Infrastructure Scope for grounding is to bond the equipment rack and, ladder rack/cable tray to the TGB by others? All other sleeves, electrical panels, building steel, etc., are bonded by others?

A4: Tel/Data contractor responsible for furnishing and installing TGB and all Telecommunications bonding and grounding. Refer to Specification Section 270526.

Q5: "TS" and "SB" locations have HDMI/USB connection to an A/V Ceiling Enclosure. Who provides this enclosure and where is it located in each room?

A5: The references to the Ceiling Enclosure and HDMI Transmitters on the IT Legend on Sheet IT-001 are incorrect. The layout as shown on Sheet IT604 is correct showing the connections between the 'TS' and 'SB'.

Additions and Alternations to the Saxe Middle School
RFP #2016-05 – Telecommunications Infrastructure Installation
State Project No. 090-0048 EA/CV
Addendum #1 – December 9, 2016
Page 2 of 2

Q6: Drawing IT-001 IT Project note #3 refers to IP addresses being required. Why would the IT contractor need IP addresses?

A6: This note is only applicable if any devices being installed by the Tel/Data contractor require network configuration and connection.

Q7: Drawing IT-001 IT Project note #18 refers to Bluetooth speakers. The speakers listed in the IT Legend do not appear to be “Bluetooth” speakers. Please clarify.

A7: The part number listed in the IT Legend for the ‘SP2’ speaker is incorrect. The part number “AMP-ER2BT6” as listed on sheet IT-604 is correct.

Bid Due Date:

Bid due date is unchanged. Bids are due no later than 11:00 a.m. on December 15, 2016 and shall be delivered to Mr. Thomas Stadler at New Canaan Town Hall, 77 Main Street, New Canaan, CT 06840.