

Additions and Alternations to the Saxe Middle School
RFP #2016-06 – Security Systems Expansion
State Project No. 090-0048 EA/CV
Addendum #1 – December 9, 2016
Page 1 of 2

Specification Section 282300 Part 1.3.A is changed to read as follows:

Contractor shall provide all field mounted cameras as indicated on the project drawings, including all mounting accessories as required, and configure new cameras on existing VMS system. Refer to Part 2 of this specification section for product information.

Responses to questions received are as follows:

Q1: As the Security System Bidder are we providing the cat 6 cables for the cameras? Also are we running the cat6 cables to camera locations or will another contractors be doing this?

A1: The Tel/Data contractor will install Cat-6 cables to all camera locations. They will be terminated with a male RJ-45 connector for direct connection to the camera network jack.

Q2: Is there any specific model of door contacts or style? Surface mount or flush mount?

A2: Door contacts to be flush mount. Acceptable manufacturers include Bosch, Interlogix, or equal.

Q3: Any specific brand or model for motion sensors?

A3: Acceptable manufacturers include Bosch, Interlogix, or equal.

Q4: Does the current VMS system have space available in regards to storage for the additional cameras that are to be provided? Or are we providing a new server for the additional cameras?

A4: No new server or additional storage is required.

Q5: For the access control doors who is providing the door hardware locking hardware?

A5: Refer to notes on Sheet SC-601, Detail 6.

Q6: For the access control panels who is providing the additional panel in the new IDF?

A6: Existing panel is to be used. Refer to drawing on Sheet SC-601, Detail 6

Q7: For the Intrusion Detection Panel who's is providing the Gemini Expansion Modules and the actual panel lock box?

A7: Refer to notes on Sheet SC-601, Detail 5. Security contractor responsible for all equipment.

Additions and Alternations to the Saxe Middle School
RFP #2016-06 – Security Systems Expansion
State Project No. 090-0048 EA/CV
Addendum #1 – December 9, 2016
Page 2 of 2

Q8: In regards to power supplies for gemini panel and schlage access control panel who is providing the power supply?

A8: Refer to notes on Sheet SC-601, Detail 5 and 6. Security contractor responsible for all equipment.

Q9: On Drawing SC-112 on the bottoms right had for a camera it states verify with architecture? Is this a camera we are providing? Also what is GYP ceiling and +9'0" AFG?

A9: All cameras as shown on the drawings are to be furnished and installed. GYP indicates this camera to be installed in a gypsum ceiling. +9'0" AFG indicates the approximate mounting height of the camera.

Bid Due Date:

Bid due date in unchanged. Bids are due no later than 11:00 a.m. on December 15, 2016 and shall be delivered to Mr. Thomas Stadler at New Canaan Town Hall, 77 Main Street, New Canaan, CT 06840.